SANITARY AND TOWN PLANNING DIVISION.

Notice dated 20th October 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Sanitary and Town Planning Division, up to the 12 noon of 27th November 1928, for the Construction of Service Reservoir connected with Water Supply to Hiriyur Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and specifications may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M. on all working days

3. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the construction of Service Reservoir for Hiriyur Water Supply" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne entirely by the contractor.

10. In all matters of disputes not specially provided for and in all matters of disputes about rates, quantities, measurements and quality of work and in all disputes of any kind, the decision of the Chief Engineer will be final and legally binding.

11. Rates for lumpsum items in the sanctioned estimates and for items for which there is no provision in the estimate shall be those that will be fixed by the Executive Engineer, either as per the schedule of rates prevailing at the time or as per data worked out with not more than ten per cent for contractor's profit.

ABSTRACT OF QUANTITIES.

Sl. No.	Items of work	Per	Quantity
	Head Works.		
1	Earthwork excavation in gravel and mooram soil ...	C.yds.	147
2	Burnt stone jelly in surki concrete (1:2)	,,	30
3	Burnt brick in surki mortar	,,	75
4	Rough stone revetment interestices wedged with chips and jelly packed.	,,	20
	Open Underground Reservoir.		
1	Earthwork excavation in gravel mixed with small boulders, and mooram.	Cyd.	1974
2	Blasting hard rock	,,	49
3	Excavating soft rock	,,	495
4	Forming spoil banks with excavated earth	,,	2469
5	Burnt stone small sized (½") jelly in surki concrete for sloping walls.	C.ft.	1670
5(a)	Burnt stone jelly (1") in surki concrete for bed ...	,,	4385

Sl. No.	Items of work	Per	Quantity
6	Burnt brick in surki mortar	C.ft.	3499
7	Burnt stone slabs 3″ x 4½″ thick two line dressed and fixed in mortar.	S.ft.	69
8	Burnt brick in mortar parapet wall 9″ thick of 2 feet high including plastering cornice, white-washing, etc., complete.	R.ft.	364
9	Plastering with cement ½″ thick (1:3)	Sqr.	87·50
10	White washing two coats	,,	36
11	Color washing	,,	36
12	Turfing the spoil bank	,,	11
	Valve Cisterns.		
1	Earthwork excavation in gravelly and mooram soil ...	C.yd.	16
2	Burnt stone jelly surki concrete	C.ft.	30
3	Burnt brick in chunam mortar	,,	236
4	Plastering with chunam mortar ½″ thick	Sqr.	2·5
5	Burnt stone slabs 4½″ thick, two line dressed and fixed in mortar.	Sq. ft.	60¾
6	Drilling holes in slabs	No.	4
	Laying and Jointing Pipes.		
1	Earthwork excavating (gravel and mooram soil) and refilling trench with watering and tamping.	C.yd.	420
2	Laying and cement jointing, 6″ cast iron pipe including cuts and collar joints.	Joints	25
3	Laying and cement jointing, 4″ cast iron pipe including cuts and collar joints.	,,	45
4	Laying and jointing 6″ flanged pipes with rubber insertion and bolts, nuts etc.	,,	4
5	Laying and jointing 4″ flanged pipes with rubber insertion, bolts, nuts, etc., complete.	,,	2
6	Laying and jointing 4″ pipe with lead	,,	5
7	Excavating, removing and stacking 4″ pipes in the existing bye-pass line including refilling forming trench, etc., complete.	R.ft.	270

H. F. MARKER,
Executive Engineer.

MYSORE RAILWAYS, HASSAN.

Abstract Notification dated 13th October 1928.

Notice is hereby given that the sealed tenders will be received at the Office of the Executive Engineer, Mysore Railways, Hassan, up to 10th November 1928, for collecting and stacking stone ballast on Birur-Shimoga Railway, for each of the sections specified as A. B. & C.

For full particulars please see detailed notification in the *Mysore Gazette*, dated 18th October 1928.

V. RAMANUJALU NAIDU,
Executive Engineer.

MEDICAL DEPARTMENT.

VICTORIA HOSPITAL, BANGALORE.

Sealed tenders, in triplicate, on half sheet foolscap size paper will be received at the office of the Victoria Hospital, Bangalore, by the undersigned at 11 A.M., on Wednesday the 14th November 1928, for the supply of articles of diet, etc., required for the use of the said Hospital, from 1st January 1929 to 31st December 1929 (inclusive).

For details, please refer to Part VI, pages 1109 and 1110 of the *Mysore Gazette*, dated 11th October 1928.

S. SUBBA RAO,
Medical Officer in-charge.